

| | | | | |
|--|---------------------------------------------------|------|-----------|-------|
| | CLARIFICATION AND DEVIATION OF TRANSFORMER | No. | Q19-23606 | |
| | | Page | 1E | Rev.0 |

1. Transformer rating : 3Ø 50Hz 60/80MVA 115kV – 2*6.0kV

2. Clarification and deviation:

| Item | Section | Client's specification | Clarification & Deviation |
|------|---------------|----------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------|
| 1 | Specification | Rated power: 80000kVA Cooling type: Oil natural Air forced ONAN/(ONAF) | ONANONAF: 60000/80000kVA will be supplied. |
| 2 | Specification | In addition, wall bushing isolators and custom made copper bus bars are required from transformer LV side to in-door substation. | Out of our quotation scope Interface: LV bushing with connection copper bar (in cable box) will be considered. |
| 3 | Inter faces | HV, LV CONNECTION | Reference to TQ19-23606 HV: Oil to air bushing and arrester LV: LV bushing with connection copper bar (in cable box) |
| 4 | Specification | Vector group: Y-n/D-D-11-11 | HV neutral side insulation class: graded (52 kV) for solid earthed |